

Board of Commissioners Consent Decree Information Sheet																																																										
Commissioner		Super District 6 – Ted Terry																																																								
Report Date		June 2026																																																								
Collection System Overview																																																										
Super District 6 contains more than 1,250 miles of sanitary sewer gravity mains and about 33,600 manholes. Most flows from Super District 6 are directed toward Atlanta’s RM Clayton WRF and the Snapfinger Plant. The County has completed assessment of the Priority Areas with the District and have identified about 700,000 LF as requiring rehabilitation while the remaining sewer mains within the Priority Areas will undergo upkeep in Maintenance Management System program. Assessment and maintenance of the sewers outside of the Priority Areas are ongoing.																																																										
Assessment Progress																																																										
Methodologies for assessment include smoke testing, in which non-toxic smoke is injected into the system to identify areas of potential I&I in the system; acoustic testing, which utilizes sound waves to detect breakages and voids; CCTV inspection, which provides a visual inspection of sewer lines; and, TISCIT which uses sonar to identify defects in large interceptor lines.																																																										
Total Assessments Progress <table><tr><th colspan="2">Total Length (LF)</th></tr><tr><td>Priority Areas</td><td>4,627,309</td></tr><tr><td>Complete</td><td>4,627,309</td></tr><tr><td>Other Areas</td><td>10,922,043</td></tr><tr><td>Complete</td><td>10,061,764</td></tr><tr><td>To Be Completed</td><td>860,279</td></tr><tr><td>Grand Total</td><td>15,549,352</td></tr></table>	Total Length (LF)		Priority Areas	4,627,309	Complete	4,627,309	Other Areas	10,922,043	Complete	10,061,764	To Be Completed	860,279	Grand Total	15,549,352	Assessments Completed by Type <table><tr><th></th><th>Length / Manhole Count</th></tr><tr><td>Priority Areas</td><td>4,627,309</td></tr><tr><td>Acoustic Inspection</td><td>1,327,659</td></tr><tr><td>CCTV Inspection</td><td>1,058,389</td></tr><tr><td>Manhole Condition Assessment</td><td>9,393</td></tr><tr><td>Manhole Rehab / Replace</td><td>2</td></tr><tr><td>Point Repair</td><td>27</td></tr><tr><td>Sewer Cleaning</td><td>63,325</td></tr><tr><td>Smoke Testing</td><td>2,032,993</td></tr><tr><td>Sonar/TISCIT</td><td>135,521</td></tr><tr><td>Other Areas</td><td>10,922,043</td></tr><tr><td>Acoustic Inspection</td><td>2,432,395</td></tr><tr><td>CCTV Inspection</td><td>4,062,427</td></tr><tr><td>Lining</td><td>78,669</td></tr><tr><td>Manhole Condition Assessment</td><td>14,906</td></tr><tr><td>Manhole Rehab / Replace</td><td>466</td></tr><tr><td>Point Repair</td><td>260</td></tr><tr><td>Sewer Cleaning</td><td>308,845</td></tr><tr><td>Smoke Testing</td><td>3,063,470</td></tr><tr><td>Sonar/TISCIT</td><td>960,604</td></tr><tr><td>Grand Total</td><td>15,549,352</td></tr></table>			Length / Manhole Count	Priority Areas	4,627,309	Acoustic Inspection	1,327,659	CCTV Inspection	1,058,389	Manhole Condition Assessment	9,393	Manhole Rehab / Replace	2	Point Repair	27	Sewer Cleaning	63,325	Smoke Testing	2,032,993	Sonar/TISCIT	135,521	Other Areas	10,922,043	Acoustic Inspection	2,432,395	CCTV Inspection	4,062,427	Lining	78,669	Manhole Condition Assessment	14,906	Manhole Rehab / Replace	466	Point Repair	260	Sewer Cleaning	308,845	Smoke Testing	3,063,470	Sonar/TISCIT	960,604	Grand Total	15,549,352
	Total Length (LF)																																																									
	Priority Areas	4,627,309																																																								
	Complete	4,627,309																																																								
	Other Areas	10,922,043																																																								
	Complete	10,061,764																																																								
	To Be Completed	860,279																																																								
	Grand Total	15,549,352																																																								
		Length / Manhole Count																																																								
	Priority Areas	4,627,309																																																								
	Acoustic Inspection	1,327,659																																																								
	CCTV Inspection	1,058,389																																																								
	Manhole Condition Assessment	9,393																																																								
	Manhole Rehab / Replace	2																																																								
	Point Repair	27																																																								
	Sewer Cleaning	63,325																																																								
	Smoke Testing	2,032,993																																																								
Sonar/TISCIT	135,521																																																									
Other Areas	10,922,043																																																									
Acoustic Inspection	2,432,395																																																									
CCTV Inspection	4,062,427																																																									
Lining	78,669																																																									
Manhole Condition Assessment	14,906																																																									
Manhole Rehab / Replace	466																																																									
Point Repair	260																																																									
Sewer Cleaning	308,845																																																									
Smoke Testing	3,063,470																																																									
Sonar/TISCIT	960,604																																																									
Grand Total	15,549,352																																																									

Preventative Maintenance

Preventative maintenance includes preventing the intrusion of roots, cleaning of lines, and ensuring access through easement clearing allow DWM to ensure the integrity of the system. Information reported is for Q1 and Q2 of 2026 only.

Countywide Q1 & Q2	Total	Super District 6 - Q1 & Q2	Total
Cleaning (LFt)	553,674	Cleaning (LFt)	254,307
Easement Clearing (SqFt)	12,996,249	Easement Clearing (SqFt)	2,407,481
Root Control (LFt)	436,920	Root Control (LFt)	292,149
Grand Total	13,986,842	Grand Total	2,953,937

Priority Area Rehabilitation Progress

Priority Areas Progress	
	Total Length (LF)
Contracted	710,068
Completed	704,559
In Progress	5,509
Grand Total	710,068

Rehabilitation Completed by Type	
Rehabilitation Method	Total Length (LF)
Abandoned	11,991
Lining	629,342
Point Repair	17,067
Point Repair & Lining	3,910
Replacement	39,559
Assessment	2,690
Grand Total	704,559

Lift Stations & Force Mains

Sewer lift stations pump untreated wastewater via a force main from lower lying areas to areas that will allow for gravity flow of the wastewater to a treatment facility. Super District 6 has 9 lift stations and 5,700 LF of force main to ensure the proper collection of wastewater. No rehabilitation of Lift Stations within Super District 6 is required. Routine maintenance is ongoing.

Overall PASARP Progress



